KOLAR DIVISION.

[ADVERTISEMENT.

Notification dated 15th July 1895.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 10th August 1895, for restoring and enlarging Kanamagunta Tank, Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1896.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Kolar between the hours of 11 A.M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring and enlarging Kanamagunta Tank, Chintamani Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate for restoring and enlarging Kanamagunta Tank, Chintamani Taluk.

Description of work.	*Unit of Work.*	*Approximate Quantity.*
Earthwork raising tank bank	C. Yd.	34,300
Repairing existing revetment	Ditto	834
New stone revetment	Ditto	1,718
Puddling wall mixed clay	Ditto	3,793
Turfing	Sqrs.	621·36
Grade stones	No.	10
Tank No. stones	Ditto	1
Gauge stones	Ditto	2
Bench Mark stones	Ditto	2
Excavation for foundations	C. Yds.	213
Ditto ditto	C. Yds.	1,050
Brick in surki mortar	C. Ft.	6,366
Rough stone apron	C. Yd.	57
Plastering with surki mortar	Sqrs.	31·65
Blasting	C. Ft.	1,000
Burnt stone slabs	S. Ft.	692
Concrete work	C. Ft.	317
Earthwork cutting	C. Yds.	5,788
Ditto embankment	C. Yds.	5,471
Compensation	L. S. Rs.	
4 Culverts	L. S. Rs.	

C. M. ANANDATIRTHA, RAO, *Offg. Executive Engineer.*

FRENCH ROCKS DIVISION.

Notice dated 17th July 1895.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, French Rocks Division, up to 10th August 1895 for the conveyance of 206,791 cubic feet of stones of various sizes and weights from the 21st mile of the Lingaraj Chattar, Kallahalli road, to the village of Kathalli, Krishnarajpet Taluk, a distance of 9½ miles.

2. Any information as to dimensions and weights of stones to be removed will be given on application to the Executive Engineer, French Rocks Division.

3. Each tender should be accompanied by a deposit of Rs. 100 in cash or Government Currency Notes as earnest money, and be superscribed "Tender for conveying stones," in default of which tenders will be rejected.

4. The final acceptance of tender will rest with the Chief Engineer of Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

THOS. INMAN, *Ex. Engineer.*